Data Dictionary

Item	Description
EA Number	The particular EA number of the project. It is the primary state identifier for transportation projects financed with federal and/or state funds.
District	The Caltrans zone that the project is being/was worked in.
Year Completion	Date the construction of project was completed.
County	Acronym of the county located in the respective Caltrans District of the project.
Route	The highway and/or freeway route number that the project is being worked on.
Dir	Direction that the lanes are facing on a route for the project.
xBegPM	The combination of prefix, postmile, and suffix, in that order for the starting postmile of the project.
xEndPM	The combination of prefix, postmile, and suffix, in that order for the ending postmile of the project.
Layer	Position of the layer of the pavement material that is being installed. Ex: 1 = top layer, 99 = milling, etc.
Material Code	Type of pavement treatment.
Thickness (ft.)	The depth of the pavement material being used for the project in ft.
Lane	Road lane the project is working on.
Beg State ODM	Beginning of the project using a State odometer.
End State ODM	Ending of the project using a State odometer.
Total Number of Lanes	Number of lanes the project was performed on.
Total Lane Miles	Number of miles from lanes that the project was worked on.
Treatment	Main pavement treatment of the project/section.
BPP	Beginning post mile prefix is a letter before the post mile that could display that the road was realigned or overlapped.
Beg PM	It is the beginning Post Mile of where the project is starting.
BPS	BPS is the beginning post mile suffix which is when that segment is unrelinquished, supplemental, or newly aligned.
EPP	Ending post mile prefix is a letter before the post mile that could display that the road was realigned or overlapped.
End PM	It is the end Post Mile of where the project is starting.
EPS	EPS is the end post mile suffix which is when that segment is unrelinquished, supplemental, or newly aligned.
Length	Length in lane miles of the pavement section.
digout	If there was a digout in the lane or not. A digout is a localized repair or patch that involves digging out or excavating an area of damaged pavement
Work Code	Treatment code for decision trees.